

2017 City Wide Resurfacing Project

City of Tuscaloosa Project #: 2017.065.001

Bid Schedule

BASE BID					
ITEM NO.	QUANTITY	UNIT OF MEASURE	DESCRIPTION	UNIT COST	TOTAL
1	600.00	Sq. Yd.	Roadbed Processing		\$ -
2	300.00	Sq. Yd.	Seed & Mulch		\$ -
3	100.00	Cu. Yd	Topsoil		\$ -
4	300.00	Sq. Yd.	Solid Sod		\$ -
5	65.00	Ton	#2 Stone		\$ -
6	125.00	Ton	825B Stone		\$ -
7	250.00	Ton	Crushed Aggregate Base Course, Type "B" Plant Mixed		\$ -
8	100.00	Ton	Crushed Aggregate, Type 8910 for Roadway Bedding		\$ -
9	250.00	Cu. Yd	Crushed Aggregate, Type 57		\$ -
10	11000.00	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" maximum aggregate size mix, ESAL range A-B, 110 lbs/SY		\$ -
11	50.00	Ton	Superpave Bituminous Concrete Binder Layer, 3/4" maximum aggregate size mix, ESAL range A-B, 220 lbs/SY		\$ -
12	50.00	Ton	Superpave Bituminous Concrete Wearing Surface Layer, widening, 1/2" maximum aggregate size mix, ESAL range A-B, 165 lbs/SY		\$ -
13	100.00	Ton	Superpave Bituminous Concrete Wearing Surface Layer, leveling, 1/2" maximum aggregate size mix, ESAL range A-B		\$ -
14	3500.00	Ton	Superpave Bituminous Concrete Binder Layer, patching, 3/4" maximum aggregate size mix, ESAL range A-B, for deep patching		\$ -
15	2.00	Each	Mail Boxes, Remove and Replace		\$ -
16	600.00	Sq. Yd.	Bituminous Treatment "A"		\$ -
17	150.00	Sq. Yd.	Bituminous Treatment "G"		\$ -
18	150.00	Sq. Yd.	Bituminous Treatment "J-G"		\$ -
19	40.00	Each	Valve Boxes Reset		\$ -
20	80.00	Each	Manhole Covers Reset		\$ -
21	112000.00	Sq. Yd.	Planing Existing Pavement (approximately 0.00" thru 4.00" Thick)		\$ -
22	100.00	Lin. Ft.	Combination Curb and Gutter, Type C (2"-0")		\$ -
23	1500.00	Lin. Ft.	Combination Curb and Gutter, Type C (2"-0") remove & replace		\$ -
24	50.00	Lin. Ft.	Concrete Curb, Type "N", Remove		\$ -
25	50.00	Lin. Ft.	Concrete Curb, Type "N"		\$ -
26	300.00	Lin. Ft.	Valley Curb		\$ -
27	50.00	Lin. Ft.	Concrete Valley Gutter, 6' wide, 6" thick		\$ -
28	200.00	Sq. Yd.	Concrete Valley Gutter, Remove and Replace		\$ -
29	2.00	Each	S-Type Inlets, Double-Wing		\$ -
30	50.00	Sq. Yd.	Riprap, Class 2, with filter fabric, Mirafi FW700 or approved equal		\$ -
31	1.00	Each	Concrete Headwall		\$ -
32	250.00	Sq. Yd.	Geotextile Stabilization Mat, Mirafi HP570 or approved equal		\$ -
33	3.00	Each	ADA Ramp - Complete, includes Curb, Concrete, Reinforcement, & Truncated Domes		\$ -
34	72.00	Sq. Ft.	ADA Detectable/Tactile Warning Surfaces		\$ -
35	265.00	Sq. Yd.	Pre-Emergent Herbicide Treatment		\$ -

2017 City Wide Resurfacing Project

City of Tuscaloosa Project #: 2017.065.001

Bid Schedule

36	9.00	Mile	Solid, Temporary, Traffic Stripe (Paint), 4" Wide		\$ -
37	3.00	Mile	Broken, Temporary, Traffic Stripe (Paint), 4" Wide		\$ -
38	1500.00	Sq. Ft.	Temporary Traffic Control Markings (Paint)		\$ -
39	100.00	Sq. Ft.	Temporary Traffic Control Legends (Paint)		\$ -
40	10.00	Mile	Soild, Yellow, Class 2, Type "A" Traffic Stripe (5" Wide)		\$ -
41	6.50	Mile	Solid, White, Class 2, Type "A", Traffic Stripe (5" Wide)		\$ -
42	2.00	Mile	Broken, Yellow, Class 2, Type "A", Traffic Stripe (5" Wide)		\$ -
43	2500.00	Lin. Ft.	Dotted, Class 2, Type "A", Traffic Stripe (5" Wide)		\$ -
44	4500.00	Sq. Ft.	Traffic Control Markings, Class 2, Type "A"		\$ -
45	250.00	Sq. Ft.	Traffic Control Legends, Class 2, Type "A"		\$ -
46	15.00	Each	Pavement Markers, Class A-H, Type 1-B		\$ -
47	15.00	Each	Pavement Markers, Class A-H, Type 2-C		\$ -
48	300.00	Each	Pavement Markers, Class A-H, Type 2-D		\$ -
49	300.00	Sq. Yd.	6" Thick Sidewalk & Driveway		\$ -
50	200.00	Lin. Ft.	4" HDPE Perforated Pipe (Includes all excavation, geotextile fabric, no. 57 Stone and fittings)		\$ -
51	5.00	Each	Remove and discard rubber speed tables and replace with asphalt speed table including striping per detail		\$ -
				TOTAL	\$ -

2017 City Wide Resurfacing Project

City of Tuscaloosa Project #: 2017.065.001

Bid Schedule

ALTERNATE #1					
ITEM NO.	QUANTITY	UNIT OF MEASURE	DESCRIPTION	UNIT COST	TOTAL
1	3100.00	Sq. Yd.	Remove unsuitable material (asphalt, base, subgrade) to a depth of 8" and haul away		\$ -
2	3100.00	Sq. Yd.	Roadbed Processing		\$ -
3	100.00	Sq. Yd.	Seed & Mulch		\$ -
4	100.00	Cu. Yd	Topsoil		\$ -
5	100.00	Sq. Yd.	Solid Sod		\$ -
6	200.00	Ton	Crushed Aggregate Base Course, Type "B" Plant Mixed		\$ -
7	350.00	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" maximum aggregate size mix, ESAL range A-B, 220 lbs/SY		\$ -
8	510.00	Ton	Superpave Bituminous Concrete Binder Layer, 1" maximum aggregate size mix, ESAL range A-B, 330 lbs/SY		\$ -
9	3100.00	Sq. Yd.	Bituminous Treatment "A"		\$ -
10	3100.00	Sq. Yd.	Planing Existing Pavement (approximately 0.00" thru 4.00" Thick)		\$ -
11	500.00	Sq. Yd.	Riprap, Class 2, with filter fabric, Mirafi FW700 or approved equal		\$ -
12	3100.00	Sq. Yd.	Geotextile Stabilization Mat, Mirafi HP570 or approved equal		\$ -
13	350.00	Lin. Ft.	4" HDPE Perforated Pipe (Includes all excavation, geotextile fabric, no. 57 Stone and fittings)		\$ -
				TOTAL	\$ -

Respectfully submitted:

Bidder: _____

Date: _____

Signature: _____

Address: _____

By: _____

Title: _____

Phone: _____

AL Contractor's License No: _____

Fax: _____

(SEAL - If Bid is by
a Corporation)

Attest: _____